

गोंय विद्यापीठ

ताळगांव पठार,

गोंय - ४०३ २०६

फोन : + ९१ - ८६६९६०९०४८



Goa University

Taleigao Plateau, Goa - 403 206

Tel : +91-8669609048

Email : registrar@unigoa.ac.in

Website : www.unigoa.ac.in

(Accredited by NAAC with Grade A+)

GU/9/2026-2027/Engg. & Tech Div/152

Date: 22/09/2026

Notice Inviting Quotation

The Registrar on behalf of Goa University invites "Percentage rate quotation" from the eligible contractors registered with Goa State PWD as under:-

Sr. No.	Name of work	Estimate cost	Class of contractor
1	Repair & Restoration of Internal roads dug up for cable laying at various locations in Goa University Campus.	Rs.2,19,459.75 (excluding G.S.T and all taxes)	V & Above (Bldgs), Goa State PWD registration

Terms and conditions:

1. The sealed quotation super scribed "**Repair & Restoration of Internal roads dug up for cable laying at various locations in Goa University Campus.**" in the enclosed schedule should reach this office by 11.00 hrs on 30/09/2026 and will be opened on the same day at 11.30 hrs.
2. The quotation must accompany E.M.D of **Rs.4389.00** in form of DD/DCR of schedule bank drawn in the favour of Registrar, Goa University, payable at Panaji. **The EMD as above should be enclosed in separate cover and attached to the cover containing the quotation.**
3. Security deposit at the rate of 10% of the gross amount of the work done shall be deducted from the bills.
4. Terms & conditions for execution of work as per CPWD form 6 & 7 shall be binding on the bidders.
5. The period for completing the work is **30 days** to be reckoned from the 07th day of issue of order.
6. The quotation should be valid for 90 days for acceptance from the date of opening.
7. The defects liability period of the work is 01 year from the date of completion of work. Security deposit will be released after the completion of defects liability period in terms of clause 17 of contract (CPWD FORM 7).

8. Quoted amount shall be exclusive of G.S.T and G.S.T as applicable shall be paid extra on total cost of the work done.

9. Self-attested copy of valid PWD Registration Certificate, PAN card & GST Registration certificate should be enclosed with the quotation.

10. The right to accept or reject the quotation in the whole or in part is reserved by the Registrar Goa University.

Yours Faithfully,

Dhuni 21/9/2016
Prof. Sunder N. Dhuri

REGISTRAR
Goa University
Taleigao Plateau
Goa 403 208

(Signature)

To,

M/s. _____

SCHEDULE

Name of Work: Repair & Restoration of Internal roads dug up for Cable laying at various locations in Goa University Campus					
SR.NO	DESCRIPTION OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Earthwork in excavation by mechanical means (hydraulic excavator/manual means in foundation trenches drain (not exceeding 1.5 m in width or 10 sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m.				
	b. All types of ordinary rock including all types of laterite rock, blasting prohibited.	20.00	Cub.m	672.00	13,440.00
					-
2	Rubble packing with hard laterite stone under floors including watering ramming and consolidating etc. in pipeline trenches and other foundations complete.	2.25	Cub.m	2211.00	4,974.75
					-
3	Providing and laying cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded granitic or basaltic stone aggregate 20mm nominal size) excluding cost of centering, shuttering and finishing in :				-
	a)all works up to plinth level	1.50	CUBM	6325.00	9,487.50
					-
4	Providing & laying cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded granitic or basaltic stone aggrt. 20 mm. nominal size) excluding cost of centering, shuttering and finishing in: a) all works up to plinth level	1.35	CUBM	6810.00	9,193.50
					-
5	Providing and laying factory made Shot blasted cement concrete interlocking paver block of minimum M35/M40 grade made by heavy duty block making machine with strong vibratory compaction and of aprproved size and design / shape laid in 50 mm thick compacted bed of coarse sand, filling the joints with coarse sand, etc. all complete as per the direction of Engineer.- in I, Wave, Rectangular, Square etc. shapes. The products should comply to IS 15658:2006 and manfucatured by ISO9001: 2008 certified plant. The shot blasting should be done using 0.4-0.5mm dia steel shots with a speed of 3200 rpm.				-
	b. 60 mm thick in Grey colour (M35 grade)	121.00	SQM	1139.00	1,37,819.00
					-

6	Laying of factory made Shot blasted cement concrete interlocking paver block of minimum M35 grade made of heavy duty block making machine with strong vibratory compaction to be layed in 50 mm thick compacted bed of coarse sand, filling the joints with coarse sand, etc. all complete as per the direction of Engineer.	80.00	SQM	326.00	26,080.00
7	Precast plain cement chequered tiles 22 mm thick of required shades laid in floors, treads of steps and landing on 20 mm thick bed of Cement mortar 1:4 (1cement : 4 coarse sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete. C) Dark shades using ordinary cement	15.00	SQM	1231.00	18,465.00
Total Amount					2,19,459.75

I hereby agree to execute the work at _____ % (ABOVE/BELOW/AT PAR) with the Estimated cost.

Quoted Percentage in words _____ Percent (ABOVE/BELOW/AT PAR) with the Estimated Cost.

CONTRACTOR


 19/9/2028
EXECUTIVE ENGINEER
 EXECUTIVE ENGINEER
 GOA UNIVERSITY