

गोंय विद्यापीठ

ताळगांव पठार,

गोंय - ४०३ २०६

फोन : + ९१ - ८६६९६०९०४८



Goa University

Taleigao Plateau, Goa - 403 206

Tel : +91-8669609048

Email : registrar@unigoa.ac.in

Website : www.unigoa.ac.in

(Accredited by NAAC with Grade A+)

GU/9/2026-2027/Engg. & Tech Div/159

Date: 29 /09/2026

Notice Inviting Quotation

The Registrar on behalf of Goa University invites "Item rate quotation" from the eligible contractors registered with Goa State PWD as under:-

Sr.No.	Name of work	Estimate cost	Class of Contractor
1.	Day-to-day minor electrical works in various buildings in the Goa University campus.	Rs.3,97,565.00 (excluding G.S.T)	IV & above (Electrical), Goa State PWD registration

Terms and conditions:

1. The sealed quotation super scribed "**Day-to-day minor electrical works in various buildings in the Goa University campus**" should reach this office by 11.00 hrs on 07 / 10 /2026 and will be opened on the same day at 11.30 hrs.
2. The quotation must accompany E.M.D of **Rs.7951.00** in form of DD/DCR of scheduled bank drawn in the favour of Registrar Goa University payable at Panaji. The EMD as aforesaid should be enclosed in separate cover and attached to the cover containing the quotation.
3. Security deposit at the rate of 10% of the gross amount of the work done shall be deducted from the bills.
4. Terms & conditions for execution of work as per CPWD form 6 & 8 shall be binding on the bidders.
5. The period of this rate contract is **180 days** to be reckoned from the 08th day of issue of order.
6. The quotation should be valid for 150 days for acceptance from the date of opening.

7. The defects liability period of the work is 01 year from the date of completion of work. Security deposit will be released after the completion of defects liability period under the terms of clause 17 of contract (CPWD FORM 8).

8. Quoted amount shall be exclusive of G.S.T and G.S.T as applicable shall be paid extra on total cost of the work done.

9. Self-attested copy of PWD Registration Certificate, PAN card & GST Registration certificates should be enclosed with the quotation and valid 660V or above license of Electricity department, Govt. of Goa.

10. The successful agency shall ensure that no damages are caused to the existing wiring cables and carry out the work by taking all precautions to avoid accidents and also follow all I.E rules in force during execution of work.

11. The right to accept or reject the quotation in the whole or in part is reserved by the Registrar Goa University.

Yours Faithfully,


24/9/2024
Prof. Sunder N. Dhuri
REGISTRAR


To,
M/s._

SCHEDULE

Name of Work:- Day-to-day minor electrical works in various buildings in Goa University campus.

SR NO	DESCRIPTION OF ITEM	Qty	UNIT	RATE(excluding G.S.T)		AMOUNT
				In figures	In words	
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface PVC conduit(medium) with modular switch, modular plates, suitable size modular GI box of specified Category and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.					
	(d) Group A -- with Cat B Modular Accessories	20.00	Point			
2	Wiring for group controlled light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface PVC conduit(medium) and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.	10.00	Point			
3	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor single core cable in the independent surface PVC conduit (medium)of appropriate size as required.					
	(a) 2 x 1.5 sq.mm + 1 x 1.5 sq.mm earthwire (20mm Conduit)	100.00	Metre			
	(b) 2 x 2.5 sq.mm + 1 x 2.5 sq.mm earthwire (20mm Conduit)	500.00	Metre			
	(c) 2 x 4 sq.mm + 1 x 4 sq.mm earthwire (20mm Conduit)	400.00	Metre			
4	Fixing modular switch 5/6 A on the existing modular plate and switch box including connections but excluding modular plate etc. as required	50.00	EACH			

Sample
JEE

Date: 20/

SR NO	DESCRIPTION OF ITEM	Qty	UNIT	RATE(excluding G.S.T)		AMOUNT
				In figures	In words	
5	Fixing modular switch 15/16 A on the existing modular plate and switch box including connections but excluding modular plate etc. as required	10.00	EACH			
6	Fixing call bell/ buzzer suitable for single phase 230 V complete as required.	5.00	EACH			
7	Erecting ISI mark modular type D.P. switch 32A with indicator, duly erected on provided plate and box with wiring connections complete.	10.00	EACH			
8	Fixing modular socket 3 pin 5/6 A on the existing modular plate and switch box including connections but excluding modular plate etc. as required	50.00	EACH			
9	Fixing modular socket 6 pin 15/16 A on the existing modular plate and switch box including connections but excluding modular plate etc. as required	50.00	EACH			
10	Fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required	10.00	EACH			
11	Fixing modular blanking plate on the existing modular plate switch box excluding modular plate etc. as required	10.00	EACH			
12	Erecting 1/2 module PVC Surface modular switch box with double mounting plate complete duly erected.	30.00	EACH			
13	Erecting 3 module PVC Surface modular switch box with double mounting plate complete duly erected.	30.00	EACH			

S. Anitha
JECE

SR NO	DESCRIPTION OF ITEM	Qty	UNIT	RATE(excluding G.S.T)		AMOUNT
				In figures	In words	
14	Erecting 4 module PVC Surface modular switch box with double mounting plate complete duly erected.	30.00	EACH			
15	Erecting 6 module PVC Surface modular switch box with double mounting plate complete duly erected.	30.00	EACH			
16	Erecting 8 module PVC Surface modular switch box with double mounting plate complete duly erected.	30.00	EACH			
17	Erecting 12 module PVC Surface modular switch box with double mounting plate complete duly erected.	30.00	EACH			
18	Erecting 18 module PVC Surface modular switch box with double mounting plate complete duly erected.	30.00	EACH			
19	Erection of departmentally supplied 4ft/2ft LED fitting on PVC block connected with necessary leads complete as per specification No. FG-IDF/LED.	10.00	EACH			
20	Erection of departmentally supplied exhaust fan with necessary materials complete.	10.00	EACH			
21	Erection of departmentally supplied ceiling fan with necessary materials complete.	10.00	EACH			
22	Erection of departmentally supplied surface / recess type decorative fitting with LED on PVC block connected with necessary leads as per specification No. FG-IDF/LED.	10.00	EACH			
23	Erecting the departmentally supplied LED street light / flood light fitting above 80 to 150W.	10.00	EACH			

Sample
JEE

SR NO	DESCRIPTION OF ITEM	Qty	UNIT	RATE(excluding G.S.T)		AMOUNT
				In figures	In words	
					Total (in Rs.)	

In words: (Rupees _____ only)

CONTRACTOR

Chandrasekhar
EXECUTIVE ENGINEER
GOA UNIVERSITY

Gandhi
JEE