गोंय विद्यापीठ
ताळगांव पठार,
गोंय - ४०३ २०६
फोन : + ९१ - ८६६९६०९०४८

Goa University
Taleigao Plateau,Goa - 403 206
Tel : +91-8669609048
Email : registrar@unigoa.ac.in
Website : www.unigoa.ac.in

(Accredited by NAAC with Grade A+)

GU/9/2026-2027/Engg. & Tech Div/183 Date: 03 / 11 /2026

Notice Inviting Quotation

The Registrar on behalf of Goa University invites "Percentage rate quotation" from the eligible contractors registered with Goa State PWD as under:-

Sr. No.	Name of work	Estimate cost	Class of contractor
1	**Repair & Maintenance work in Women's Hostel In Goa University Campus.**	**Rs.3,99,136.52** (excluding G.S.T and all taxes)	V & Above (Bldgs), Goa State PWD registration

Terms and conditions:

1. The sealed quotation super scribed **"Repair & Maintenance work in Women's Hostel In Goa University Campus."** in the enclosed schedule should reach this office by 11.00 hrs on 12 / 11 /2026 and will be opened on the same day at 11.30 hrs.

2. The quotation must accompany E.M.D of **Rs.7983.00** in form of DD/DCR of schedule bank drawn in the favour of Registrar, Goa University, payable at Panaji. **The EMD as above should be enclosed in separate cover and attached to the cover containing the quotation.**

3. Security deposit at the rate of 10% of the gross amount of the work done shall be deducted from the bills.

4. Terms & conditions for execution of work as per CPWD form 6 & 7 shall be binding on the bidders.

5. The period for completing the work is **30 days** to be reckoned from the 07th day of issue of order.

6. The quotation should be valid for 90 days for acceptance from the date of opening.

7. The defects liability period of the work is 01 year from the date of completion of work. Security deposit will be released after the completion of defects liability period in terms of clause 17 of contract (CPWD FORM 7).

8. Quoted amount shall be exclusive of G.S.T and G.S.T as applicable shall be paid extra on total cost of the work done.

9. Self-attested copy of valid PWD Registration Certificate, PAN card & GST Registration certificate should be enclosed with the quotation.

10. The right to accept or reject the quotation in the whole or in part is reserved by the Registrar Goa University.

Yours Faithfully,

29/10/2026

Prof. Sunder N. Dhuri
REGISTRAR

REGISTRAR
Goa University
Taleigao Plateau
Goa 403 206

To,
M/s._____
_____
_____
_____

Name of Work:Repair and Maintenance work in Womens Hostel In Goa University Campus.					
SCHEDULE					
Sr. No	**Description of work**	**Unit**	**Quantity**	**Rate**	**Amount**
1	Providing and applying sika Combiflex to expansion joint sealing including removal of existing joint material, cleaning and preparation of joint material, repair of damaged concrete, supply and fixing of sika combiflex tape with approved sikadur/Combiflex adhesive (A+B) including all material labour and finishing, complete as directed by Engineer in charge.	Meter	29.80	2242.50	66,826.50
					-
2	Providing and fixing expansion joint cover system comprising 150mm wide aluminium plate on top side securely fixed with stainless steel screw including all accessories, surface preparation alignment finishing and complete installation including cost of all material labour and incidental charges complete as directed by Engineer in Charge.	Meter	29.80	2415.00	71,967.00
					-
3	Providing and applying exterior wall crack repair, including opening/widening of cracks in V-groove with grinder, cleaning and filling with sika flex sealant, applying one coat of sika primer-133 and finishing with sika cool coat PU coating complete with all material labour tool scaffolding and incidental charges as directed by Engineer incharge.	Sqm	51.00	805.00	41,055.00
					-

4	Repairs to plaster in patches of 2.5 sq.m. and under including cutting the patch in proper shape and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50m lead. With cement mortor 1:4 (1cement:4fine sand)	Sqm	21.00	314.00	6,594.00
5	Dismantling doors, windows and clearestory windows (steel or wood) shutters including chowkhats architrave holdfast etc. complete and staking within 50 mt. Lead				-
	a)Of area 3 sq.m. and below	Each	2.00	206.00	412.00
					-
6	Providing 25 mm thick cuddapah slabs machine cut and polished on either side in partitions including making necessary grooves in the wall and fixing with cement mortar, complete as directed by the engineer-in-charge	Sqm	1.00	947.00	947.00
					-
7	Providing and fixing vitrified antiskid tiles (320x320) and 10mm thick tiles in floor, treads of steps, landing on 25mm thick bed of cement mortar 1:3 and jointed with cement slurry complete.	Sqm	1.44	1128.00	1,624.32
					-
8	Providing and fixing 600 x 450 mm bevelled edge mirror of superior glass (of approved quality) complete with 6 mm thick asbestos sheet ground fixed to wooden cleats with C. P. brass screws and washers.	Each	11.00	2130.00	23,430.00
					-

9	**Removing old loose bottom or side cover of RCC** slab, beam, columns etc. rubbing surface of concrete steel using wire brush and applying 2 coats of Alkaline rust converting primer (Feovert) after a waiting time of 6 hrs between coats and then applying another anti corrosive protective coating system) for reinforcement bars (IPNet-RB) Conforms to IS-2770 Part-1 (Pull out Test) ASTM-3963-86 (Adhesion Test) and then applying concrete penetrating corrosion inhibitor (EPCO-KP100) and applying bonding new to old concrete (Epibond) Conforms to ASTM-C-882-87 and plastering on the fresh bond coat with Polymer Modified Mortar (Monobond) with 20mm C.M 1:3 and finishing coat of 6mm C.P 1:3 (1 Cement : 3 Sand) incl. cost of transport etc. as per dir of EIC. All the chemicals will be of Krishna Conchem Products Pvt. Ltd. or Equivalent.	Sqm	19.00	2086.00	39,634.00
					-
10	**Providing and fixing P.V.C. connection pipe** with brass unions 15 mm nominal bore: c) 45cm (18")Length	Each	3.00	235.00	705.00
					-
11	Providing and fixing Hand Shower (Health Faucet) with 8mm dia, ABS/brass body with double lock 1.00m long Flexible tube (Brass plated stainles steel flexible hose) and wall hook of approved quality confirming to IS standards.	Each	3.00	1648.00	4,944.00
					-
12	Providing & fixing soap dish chromium plated with brackets fixed to wooden cleats with CP brass screw , ARK supreme / Omco make	Each	20.00	873.00	17,460.00
					-

13	Providing & fixing c.p. brass towel rail complete with C.P. brass brackets fixed to wooden cleats with C. P. brass screws a) 750x20mm size	Each	13.00	2368.00	30,784.00
					-
14	Providing and fixing 10 litres pvc. Automatic flushing cistern with fittings	Each	20.00	1267.00	25,340.00
					-
15	Providing and fixing precast reinforced concrete door frames of ASTRA make or equivalent in M25 grade concrete and reinforced with minimum three bars of 6 mm dia and confirming to IS:6523. The frames shall be manufactured in approved factory with all the necessary arrangements for fixing hinges, tower bolts by way of inserted PVC blocks and holes for receiving sliding bolts as specified. Sectional size of frame with single rebate : 60X 100 mm				-
	ii)2100 X 900 mm	Meter	10.60	366.00	3,879.60
					-
16	Providing and fixing vitreous China water closet squatting (European type W.C pan) with seat and lid C.P brass hinges and rubber buffers 10 lts high level PVC flushing cistern (of cera conventional "s" /p trap) with fittings rack bolts, 32 mm, dia PVC telescopic flush pipe with fittings and clamps 25 mm PVC over flow pipe with specials & mosquito proof coupling of approved municipal design and nylon chain and pull complete, cutting & making good the walls & floors where required. (HINDUSTAN/CERA)				-
	a) **WC pan** – Hindustan /Cera conventional EWC of white colour with white plastic lid & seat.	Each	1.00	7925.00	7,925.00
					-

17	Providing and fixing NICKEL chrome plated copper alloy Fancy two way long body bib cock with wall flance Jaquar make or equivalent. Confirming to IS 8931;1993 a)15mm Nominal bore	Each	6.00	1543.00	9,258.00
					-
18	Providing and fixing 1st quality ceramic glazed wall tiles (Johnson, Somany, Kajaria)conforming to IS:15622 (thickness to be specified by the manufacture of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-charge in skirting, risers of steps and dados over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @3.3kg per sq.m including pointing in white cement mixed with pigment of matching shade complete.				-
	a) Wall Ceramic Glazed Tiles : 200 x 300	Sqm	6.20	792.00	4,910.40
	b) Wall Ceramic Glazed Tiles : 300 x 450	Sqm	3.00	892.00	2,676.00
					-
19	Removing white or colour wash by scrapping, sand papering and preparing surface smooth including necessary repairs to scratches etc. complete.	Sqm	93.50	19.00	1,776.50
					-
20	**Providing and applying white cement** based putty of average thickness 1.00mm of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	93.50	89.00	8,321.50
					-
21	Applying one coat of cement primer of approved brand and manufacture on wall surface	Sqm	93.50	53.00	4,955.50
					-
22	Wall painting (two or more coats) with plastic emulsion paint of approved brand and manufacture on new work to give an even shade.	Sqm	93.50	114.00	10,659.00

					-
23	Painting three or more coats with acryllic exterior paint of approved brand and manufacture (Such as Dulex/ Asian Paints/ Sherwin Willians) including applying one coat of cement primer and one coat of surface treatment etc. complete	Sqm	51.00	208.00	10,608.00
					-
24	Painting two or more coats (excluding priming coat) with superior quality ready mixed paint for wood work of approved brand & manufacture in all shades on new work to give an even shade. (Satin finish)	Sqm	24.20	101.00	2,444.20
			Total Amount		**3,99,136.52**

I hereby agree to execute the work at _____% (ABOVE/BELOW/AT PAR) with the estimate cost.

Quoted Percentage in words_____ percent (ABOVE/BELOW/AT PAR) with the estimate cost.

29/10/2026

CONTRACTOR

Executive ~~UNIVERSITY~~ ENGINEER i/c

EXECUTIVE ENGINEER
GOA UNIVERSITY