

गोंय विद्यापीठ

ताळगांव पठार,

गोंय - ४०३ २०६

फोन : + ९१ - ८६६९६०९०४८



Goa University

Taleigao Plateau, Goa - 403 206

Tel : +91-8669609048

Email : registrar@unigoa.ac.in

Website : www.unigoa.ac.in

(Accredited by NAAC with Grade A+)

GU/9/2026-2027/Engg. & Tech Div/043

Date: 20/05/2026

Notice Inviting Quotation

The Registrar on behalf of Goa University invites "Percentage rate quotation" from the eligible contractors registered with Goa State PWD as under:-

| Sr.No. | Name of work | Estimate cost | Class of contractor |
|--------|--|--|--|
| 1 | Providing electrical wiring for Agilent Cross Lab in SCS, Block E | Rs.1,23,412.00 (excluding G.S.T and all taxes) | IV & above (Electrical), Goa State PWD registration |

Terms and conditions:

1. The sealed quotation super scribed "**Providing electrical wiring for Agilent Cross Lab in SCS, Block E**" in the enclosed schedule should reach this office by 11.00 hrs on 29/05/2026 and will be opened on the same day at 11.30 hrs.
2. The quotation must accompany E.M.D of **Rs2468.00** in form of DD/DCR of schedule bank drawn in the favour of Registrar, Goa University, payable at Panaji. **The EMD as above should be enclosed in separate cover and attached to the cover containing the quotation.**
3. Security deposit at the rate of 10% of the gross amount of the work done shall be deducted from the bills.
4. Terms & conditions for execution of work as per CPWD form 6 & 7 shall be binding on the bidders.
5. The period for completing the work is **30** days to be reckoned from the 07th day of issue of order.
6. The quotation should be valid for 90 days for acceptance from the date of opening.
7. The defects liability period of the work is 01 year from the date of completion of work. Security deposit will be released after the completion of defects liability period in terms of clause 17 of contract (CPWD FORM 7).



8. Quoted amount shall be exclusive of G.S.T and G.S.T as applicable shall be paid extra on total cost of the work done.

9. Self-attested copy of valid Goa State PWD Registration certificate, valid license for 660v or above issued by electricity department, Govt. of Goa, PAN card & GST Registration should be enclosed with the quotation.

10. The successful agency shall ensure that no damages are caused to the existing wiring cables and carry out the work by taking all precautions to avoid accidents and also follow all I.E rules in force during execution of work.

11. The right to accept or reject the quotation in the whole or in part is reserved by the Registrar Goa University.

Yours Faithfully,


Prof. Sunder N. Dhuri
REGISTRAR


To,
M/s.

SCHEDULE

Name of Work:- Providing electrical wiring for Agilent Cross Lab in SCS, Block E

| <u>SR NO</u> | <u>DESCRIPTION OF ITEM</u> | <u>Qty</u> | <u>UNIT</u> | <u>RATE (excluding G.S.T)</u> | | <u>AMOUNT</u> |
|--------------|--|------------|-------------|-------------------------------|-----------------|---------------|
| | | | | <u>In figures</u> | <u>In words</u> | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1.00 | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor single core cable in the independent surface PVC conduit (medium)of appropriate size as required. | | | | | |
| 1.01 | (c) 2 x 4 sq.mm + 1 x 4 sq.mm earthwire (20mm Conduit) | 18.00 | Meter | 366.00 | | 6588.00 |
| 1.02 | (d) 2 x 6 sq.mm + 1 x 6 sq.mm earthwire (25mm Conduit) | 4.00 | Meter | 485.00 | | 1940.00 |
| 2.00 | Supplying and fixing following way SPN sheet steel MCB distribution board Consumer Unit 240 V on surface/ recess complete with tinned copper busbar neutral busbar earth bar dinnbar hinged front acrylic cover for the MCB knobs detachable gland plate interconnections phosphotized and powder painted including earthing etc. as required (but without MCB/RCCB/Isolator) (b) 2 + 8 way Cat A | 1.00 | Each | 4325.00 | | 4325.00 |

| <u>SR NO</u> | <u>DESCRIPTION OF ITEM</u> | <u>Qty</u> | <u>UNIT</u> | <u>RATE (excluding G.S.T)</u> | | <u>AMOUNT</u> |
|--------------|---|------------|-------------|-------------------------------|-----------------|---------------|
| | | | | <u>In figures</u> | <u>In words</u> | |
| 3.00 | Supplying and fixing 6 A to 32 A, C series MCB suitable for lighting and other loads of following poles in the existing MCB DB complete with connections testing and commissioning etc as required. (f) SP, Cat B | 4.00 | Each | 352.00 | | 1408.00 |
| 4.00 | Supply of 2 core unarmoured PVC/XLPE insulated, PVC sheathed copper conductor cable of 1.1 KV grade with ISI mark conforming to IS:1554(Part I) ,IS:7098(Part I) with latest amendments of following size. 2 Core 16 sq.mm | 78.00 | Metre | 650.00 | | 50700.00 |
| 5.00 | Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of size not exceeding 25 sq.mm on surface, etc. complete as required | 78.00 | Metre | 88.00 | | 6864.00 |
| 6.00 | Supply and making cable end terminations with compression gland and copper lugs for following sizes of PVC insulated PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade, complete as required. (5) 2 x 16 Sq. mm. | 6.00 | Each | 291.00 | | 1746.00 |

| <u>SR NO</u> | <u>DESCRIPTION OF ITEM</u> | <u>Qty</u> | <u>UNIT</u> | <u>RATE (excluding G.S.T)</u> | | <u>AMOUNT</u> |
|--------------|--|------------|-------------|-------------------------------|-----------------|---------------|
| | | | | <u>In figures</u> | <u>In words</u> | |
| 7.00 | Providing and fixing 4 mm dia copper wire on surface or in recess for loop arthing . as required | 170.00 | Metre | 140.00 | | 23800.00 |
| 8.00 | Supplying and fixing suitable size modular GI box with modular plate and cover in front on surface or in recess including providing and fixing 2 no 6 pin 15/16 A modular socket outlet and 2 nos 15/ 16 A modular switch connection painting etc. as required. (b) Cat B | 3.00 | Each | 1430.00 | | 4290.00 |
| 9.00 | Supplying and fixing of following sizes of rigid PVC conduit alongwith accessories in surface(medium)/recess(heavy) including cutting the wall and making good the same in case of recessed conduit as required. (a) 20 mm | 85.00 | Metre | 172.00 | | 14620.00 |
| 10.00 | Supplying and fixing 63 A, C series MCB suitable for lighting and other loads of following poles in the existing MCB DB complete with connections testing and commissioning etc as required. (c) DP, Cat A | 3.00 | Each | 2105.00 | | 6315.00 |

| <u>SR NO</u> | <u>DESCRIPTION OF ITEM</u> | <u>Qty</u> | <u>UNIT</u> | <u>RATE (excluding G.S.T)</u> | | <u>AMOUNT</u> |
|--------------|---|------------|-------------|-------------------------------|-----------------------|----------------------|
| | | | | <u>In figures</u> | <u>In words</u> | |
| 11.00 | Supplying & erecting CRCA sheet metal one way enclosures of 1.2mm thickness suitable for DP MCB/TP MCB/FP MCB/RCCB/RCBO complete erected on provided angle iron/GI frame. | 2.00 | Each | 408.00 | | 816.00 |
| | | | | | Total (in Rs.) | ₹ 1,23,412.00 |

(Amble)
JUNIOR
G.S.T

I hereby agree to execute the work at _____ % (ABOVE/BELOW/AT PAR) with the estimated cost.

Quoted Percentage in words _____ percent (ABOVE/BELOW/AT PAR) with the estimated cost.

CONTRACTOR

(Signature)
EXECUTIVE ENGINEER
GUNSHYEN
EXECUTIVE ENGINEER